

PROJECT

91-94 NORTH WALL QUAY



CLIENT

Wintertide

WHAT WE DID

We provided Runtal radiators throughout this iconic office development. We worked closely with client and design team to find a solution that would stand the test of time.

THE CHALLENGE

The height of the building places high pressure on the LPHW system. These pressures would be too great for a standard tubular steel radiator. We used a high pressure radiator solution with 2mm steel wall thickness to ensure no leaks or deformations would occur over time. This strategy proved very successful on the project.

THE TEAM

Versatile | IN2 | Lynskey | Bennett Construction